



Certificate

408.01C01

Marsh Industries Limited

Head Office Addington Park Industrial Park. Little Addington NN14 4AS UK

EN 12566-3, Annex B

Small wastewater treatment systems for up to 50 PT

Small wastewater treatment system Ensign Range E L

Fluidised bed reactor system in a GRP tank

Test report PIA2022-408B25

Evaluation of the nominal sequences of the 38-week testing

Nominal organic daily load (influent)	0.30 kg BOD ₅ /d		
Nominal hydraulic daily load	0.9 m ³ /d		
Material	GRP		
Treatment efficiency		Efficiency	Effluent
	COD	92.2 %	63 mg/l
	BOD ₅	95.6 %	14 mg/l
	TN _b	53.5 %	28 mg/l
	NH ₄ -N	97.8 %	1.0 mg/l
	P _{tot}	28.7 %	5.4 mg/l
	SS	94.5 %	21 mg/l

Evaluation of the complete 38-week testing

Electrical consumption	1.9 kWh/d
Number of desludging	0

Tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH

(PIA GmbH)

Hergenrather Weg 30

52074 Aachen, Germany

This document replaces neither the declaration of performance nor the CE marking.



Martina Wermter

August 2022



Notified Body
No.: 1739



Deutsche
Akkreditierungsstelle
D-PL-17712-01-00